BHADRAVATI DIVISION.

Abstract Notification dated 28th April 1927.

It is hereby notified for general information that timber sales in the following Depots of of the Division will be held during May 1927, subject to the conditions contained in the detailed notification of date advertised on pages 337 to 338, Part VI of the *Mysore Gazette*, dated 5th May 1927.

1. Bhadravati 5,000 C. ft. on 30th May 1927.
2. Channagiri 5,000 C. ft. on 27th May 1927.

M. MACHAIYA,
District Forest Officer.

KADUR DIVISION.

Abstract Notification.

The attention of the public is invited to the detailed notification published on pages 322 to 323, Part VI of the *Mysore Gazette*, dated 28th April 1927, regarding the sale of timber at Kadur Depot on 30th May 1927.

P. WOOTHIAH,
District Forest Officer.

ENGINEERING DEPARTMENT.

SHIMOGA DIVISION.

Abstract Notification.

The attention of the public is invited to the notice calling for tenders for the construction of the Intermediate College at Shimoga published in *Mysore Gazette*, dated 5th May 1927, Part VI, page 358.

M. A. SRINIVASACHARI,
Executive Engineer.

MYSORE DIVISION.

Dated 4th May 1927.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Mysore Division, up to 1 P.M. 31st May 1927, for Restoring Martikere Tank, Hunsur Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1928.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Mysore, between the hours of 11 A.M. and 5 P.M. on all Office days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.—

Description of work	Unit of work	Rate per unit

4. Each tender must be accompanied by a deposit of Rs. 500 in Cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for restoring Martikere Tank, Hunsur Taluk" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Chief Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Abstract Estimate for Restoring Martikere, Hunsur Taluk.

No.	Items of work	Per	Rate	Quantity	Cost
	Bund.		Rs. a. p.		
1	Clearing thick jungle and rooting out trees required all over the site.	Lump sum		...	150
2	Blasting and removing boulders in the alignment of bund, clearance, parallel trenches and core wall if necessary.	Lump sum		...	150
3	Earthwork (lead 400' to 600') ...	C.yds.	0 6 0	1,404	411
4	Revetment ...	,,	1 8 0	295	443
5	Gravel backing 6" thick	,,	0 12 0	88	66
6	Turfing slopes	Sqr.	1 0 0	57	57
7	Grade stones	Each	2 8 0	7	17
8	Index stones	,,	1 0 0	7	7
9	B. M. stones	,,	5 0 0	2	10
10	Register No. stone	,,	5 0 0	1	5
11	Weir gauge stone	,,	6 0 0	1	6
12	Diversion of cart-track from Kottegal to Maralvadi.	Lump sum		...	300
13	Unforeseen charges and rounding ...	Lump sum		...	135
	Total for bund ...	...	...	...	1,760
	Breach-filling.				
1	Blasting boulders, clearance beyond halla, trenches, etc.	Lump sum		...	150
2	Clearing breach halla stones, etc., and baling water.	Lump sum		...	500
3	Ring-bunding and protective works by stages as the small perennial flow and drainage have to pass through the gap only.	Lump sum		...	1,000
4	Clearing bed of silt soil and stones ...	C.yds.	0 8 0	2,884	1,442
5	Earthwork with mixed soil (lead 400 feet to 600 feet).	,,	0 7 0	9,118	3,989
6	Revetment	,,	1 8 0	850	1,275
7	Gravel backing 6" thick	,,	0 12 0	180	135
8	Turfing slopes	Sqr.	1 0 0	189	189
9	Levelling mounds in rear, etc. ...	Lump sum		...	50
10	Cutting puddle trench	Lump sum		...	20
11	Puddle wall	C.yds.	0 12 0	896	672
12	Unforeseen charges and rounding ...	Lump sum		...	228
	Total for breach filling ...	...	...	...	9,650
	Escape at left flank.				
1	Cutting in very hard gravel and stoney soil.	C.yds.	0 12 0	2,120	1,590
2	Rough stone work	,,	1 8 0	82	123
3	Brick in surki mortar	C.ft.	0 7 0	240	105
4	Surki mortar plastering	Sqr.,	5 0 0	3·00	15
5	Unforeseen charges and rounding ...	Lump sum		...	67
	Total for escape ...	...	...	...	1,900

No.	Items of work	Per	Rate	Quantity	Cost
	Sluice.		Rs. a. p.		
1	Excavating gravelly soil mixed with stone	C.yd.	0 12 0	625	469
2	Blasting boulders	Lump sum		...	25
3	Jelly concrete in surki mortar ...	C.ft.	0 5 0	716	224
4	Burnt brick in surki mortar ...	"	0 7 0	1,546	676
5	Burnt stone slabs dressed and fixed ...	S.ft.	1 4 0	255	319
6	Making holes in the slabs... ...	each	1 8 0	5	8
7	Plastering with surki mortar ...	Sqr.	5 0 0	9·53	48
8	Cement plastering ½ inch thick ...	Sqr.	15 0 0	4·18	63
9	Filling earth with watering and tamping. Earth got from bed of tank ...	C.yd.	0 6 0	468	175
10	Wooden plug with iron rod and locking arrangement etc., complete ...	Lump sum		...	75
11	Cutting approach to sluice ...	Lump sum		...	50
	Total ...	...	...	...	2,132
	Deduct for cost of old materials from sluice	...	...	...	50
	Total ...	...	...	...	2,082
	Rounding ...	...	...	...	58
	Total for sluice ...	...	...	...	2,140
	Right sluice channel.				
1	Concrete and brick masonry through channel	R.ft.	5 0 0	330	1,650
2	Masonry aqueduct with short piers ..	R.ft.	10 0 0	75	750
3	Excavating sluice channel ...	Mile	400 0 0	1¼	500
4	Clearing jungle	Lump sum		...	100
5	Pipe sluices in turf and revetment ...	Each	30 0 0	6	180
6	Short relieving weirs	Each	50 0 0	3	150
7	Compensation for dry lands ...	Gunta	2 8 0	10	25
8	Cart track ramps	Each	15 0 0	3	45
9	Unforeseen charges and rounding ...	Lump sum		...	100
	Total for right sluice channel ...	...	...	...	3,500
	Sheds and medical charges.				
	For imported labour and unhealthy locality	Lump sum		...	1,000

L. A. H. WINCKLER,
Executive Engineer.

MISCELLANEOUS DEPARTMENTS.

EXCISE DEPARTMENT.

TUMKUR DISTRICT.

Notification No. 1728 *dated* 2*nd May* 1927.

Tenders are hereby invited for the exclusive privilege of vending ganja in the undermentioned shops of Tiptur Taluk during the twelve months beginning from 1st July 1927 and ending in the 30th June 1928.

Each tender should be accompanied by a deposit of Rs. 50 in currency notes enclosed in a cover superscribed with the words "Tender for Excise shops in the year 1927-28" and sent to the address of the Deputy Commissioner, Tumkur District, so as to reach him before 12 noon of the 23rd May 1927 after which time no tenders will be accepted.